SITE PLAN

RAYMOND PARK

TAX MAP 2 LOTS 5-59, 5-68, 5-71, 5-73, 5-74 419 MAMMOTH ROAD PELHAM, NEW HAMPSHIRE

RESOURCE LIST

PELHAM PLANNING DEPARTMENT 6 VILLAGE GREEN PELHAM, NH 03076 (603) 635-7811 JEFF GOWAN, PLANNING DIRECTOR JENNIFER HOVEY, PLANNING ASSISTANT SANDRA KINSLEY, CODE ENFORCEMENT ADMINISTRATIVE ASST. PELHAM ZONING BOARD OF ADJUSTMENT 6 VILLAGE GREEN PELHAM, NH 03076 (603) 635-7811 PETER McNAMARA, CHAIR

PELHAM POLICE DEPARTMENT 14 VILLAGE GREEN PELHAM, NH 03076 (603) 635-2411 CHIEF EVAN HAGLUND

PELHAM FIRE DEPARTMENT 65 OLD BRIDGE ST NORTH P.O. BOX 321 PELHAM, NH 03076 (603) 635-2703 CHIEF E. DAVID FISHER ASSISTANT CHIEF RAYMOND J. CASHMAN SR.

ELECTRIC GRANITE STATE ELECTRIC CO. CONNECTUTILITIES, INC. 7117 FLORIDA BLVD. BATON ROUGE, LA 70806

TELEPHONE **VERIZON COMMUNICATIONS** 100 GAY STREET MANCHESTER, NH 03103 (603) 645-2713

Copyright 2006 ©Thomas F. Moran, Inc.

48 Constitution Drive, Bedford, N.H. 03110

Thomas F. Moran, Inc.

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever

without the prior written permission of Thomas F. Moran, Inc.

ABUTTERS

MAP 2, LOT 5-28 BRENDA BROX, MATTHEW MANNING, KENNETH & PAUL GILL 1080 MAMMOTH ROAD DRACUT, MA. 01826

TYNCO REALTY, LLC 108 ALSACE STREET MANCHESTER, NH 03102

NORMAN & JOYCE COOMBS 415 MAMMOTH ROAD PELHAM, NH 03076

MAP 2, LOT 5-60 ALAN T. & ELAINE M. MARCUM 425 MAMMOTH ROAD PELHAM, NH 03076 MAP 2, LOT 5-66 AMY & DENNIS L'HEUREUX

27 KEYES HILL ROAD PELHAM, NH 03076 RICHARD D. BECOTTE et al. 31 KEYES HILL ROAD

PELHAM, NH 03076 MAP 2, LOT 5-69 TOWN OF PELHAM 6 VILLAGE GREEN

PELHAM, NH 03076 MAP 2, LOT 5-71 TOWN OF PELHAM 6 VILLAGE GREEN

MAP 2, LOT 5-72 GAIL HEIMBACK & SUSAN WHITNEY et al. 44 GIBSON ROAD HUDSON, NH 03051

MAP 2, LOT 5-73 TOWN OF PELHAM 6 VILLAGE GREEN PELHAM, NH 03076

TOWN OF PELHAM 6 VILLAGE GREEN PELHAM, NH 03076 MAP 2, LOT 5-75-1 ROBERT P. MCGRATH JR.

45 KEYES HILL ROAD PELHAM, NH 03076 KEYES HILL REALTY TRUST

47 KEYES HILL ROAD PELHAM, NH 03076 KEYES HILL REALTY TRUST 47 KEYES HILL ROAD PELHAM, NH 03076

MAP 2, LOT 5-75-4 KEYES HILL REALTY TRUST 47 KEYES HILL ROAD PELHAM, NH 03076

OWNER

TOWN OF PELHAM 6 VILLAGE GREEN PELHAM, NH 03076

MAP 2, LOT 5-75-7 KEYES HILL REALTY TRUST 47 KEYES HILL ROAD PELHAM, NH 03076

36 KEYES HILL ROAD

MAP 2, LOT 5-90 CAROL MANTHORNE 30 KEYES HILL ROAD PELHAM, NH 03076

PELHAM, NH 03076

DAWN M. HOLDSWORTH 26 KEYES HILL ROAD PELHAM, NH 03076

MAP 2, LOT 5-93 TOWN OF PELHAM 6 VILLAGE GREEN PELHAM, NH 03076

DONNA WIEGMANN et al. 4 CASTLE HILL ROAD

19 KEYES HILL ROAD

PELHAM, NH 03076 MAP 6, LOT 4-169 WALTER & HELEN REMEIS REV. TRUST 50 GIBSON ROAD

MAP 6, LOT 4-170 J. ALBERT LYNCH JR. 20 ROOSEVELT AVENUE APT. 24 HUDSON, NH 03051

MAP 6, LOT 4-171 DENYSE L. MERULLO S. ENTERPRISE DRIVE SALEM, NH 03079 MAP 6, LOT 5-72-1 PERTER & KRISTIE REMEIS 1 MAPLE AVENUE

HUDSON, NH 03051

MAP 2, LOT 5-88 CHRISTOPHER SHAY et al. 34 KEYES HILL ROAD MAP 2, LOT 5-88-1 SUSAN TILBERT

MAP 2, LOT 5-91


MAP 2, LOT 5-92 JOHN & DALE BEGLEY 1 CASTLE HILL ROAD PELHAM, NH 03076

MAP 2, LOT 5-146

MAP 2, LOT 5-147 JOSEPH P. & NANCY R. HOULNE

MAP 3, LOT 5-29 HENRY MAHEU P.O. BOX 238

HUDSON, NH 03051



PREPARED FOR

TOWN OF PELHAM 6 VILLAGE GREEN PELHAM, NH 03076

INDEX OF SHEETS

SHEET TITLE

COVER SHEET EXISTING CONDITIONS SITE LAYOUT PLAN

GRADING AND DRAINAGE PLAN PLAYING FIELD SUBGRADE PLAN STORM WATER MANAGEMENT PLAN

11-13 **DETAIL SHEETS**

PERMITS/APPROVALS

SUBMITTED APPROVED EXPIRES NUMBER

NHDES SITE SPECIFIC NHDES SEPTIC NHDOT DRIVEWAY TOWN SITE PLAN

PROGRESS PRINT

DECEMBER 11, 2006

TAX MAP 2 LOTS 5-59, 5-68, 5-71, 5-73, 5-74 COVER SHEET

RAYMOND PARK 419 MAMMOTH ROAD PELHAM, NH

OWNED BY AND PREPARED FOR TOWN OF PELHAM

6 VILLAGE GREEN, PELHAM, NH 03076 MAY 25, 2006 SCALE: AS NOTED


Structural Engineers Traffic Engineers


48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747


Bedford, NH • Manchester, NH • Keene, NH • Salem, NH • Portsmouth, NH


MAP 2 LOTS 5-59, 5-68


REV. DATE DESCRIPTION DR CK























CONSTRUCTION SEQUENCE NOTES

- 1. INSTALL STABILIZED CONSTRUCTION ENTRANCE.
- 2. CUT AND CLEAR TREES WITHIN AREA OF DISTURBANCE UNLESS OTHERWISE NOTED.
- 3. CONSTRUCT TEMPORARY AND PERMANENT EROSION CONTROL FACILITIES PRIOR TO ANY EARTH MOVING OPERATION INSPECT AND MAINTAIN ALL EROSION AND SEDIMENTATION CONTROL MEASURES PERIODICALLY AND IMMEDIATELY
- 4. ROUGH GRADE FIELDS, DRIVEWAYS & PARKING AREAS. ALL SLOPES SHALL BE STABILIZED IMMEDIATELY AFTER GRADING. ALL DISTURBED AREAS SHALL BE STABILIZED NO LATER THAN 72 HOURS AFTER CONSTRUCTION ACTIVITY CEASES. IF EARTHWORK TEMPORARILY CEASES ON A PORTION OF OR THE ENTIRE SITE, AND WILL NOT RESUME WITHIN 21 DAYS. THE AREA SHALL BE STABILIZED. (STABILIZE PROPOSED PAVEMENT AREAS WITH COMPACTED GRAVELS AND OTHER DISTURBED AREAS WITH TEMPORARY GRASS SEEDING.)
- 5. CONSTRUCT CULVERTS, DETENTION BASINS AND TREATMENT SWALES. PLACE HEADWALLS, RIP-RAP AND OTHER DRAINAGE FACILITIES ACCORDING TO PLAN. THE CONTRACTOR SHALL STABILIZE ALL DITCHES, SWALES, AND BASINS
- 6. CONSTRUCT GRAVEL PARKING TO FINISH GRADE ACCORDING TO PLAN. ALL SLOPES SHALL BE STABILIZED IMMEDIATELY AFTER GRADING
- 7. COMPLETE PERMANENT SEEDING.
- 8. REMOVE TEMPORARY EROSION CONTROL MEASURES ONCE ALL AREAS ARE STABILIZED. AN AREA SHALL BE CONSIDERED STABILIZED IF:
- A) BASE COURSE GRAVELS HAVE BEEN INSTALLED;
- B) A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED; C) A MINIMUM OF 3" OF NON-EROSIVE MATERIAL SUCH AS STONE OR RIPRAP HAS BEEN INSTALLED OR D) EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

GENERAL NOTES

- . THE CONTRACTOR SHALL CONTACT ALL UTILITY COMPANIES OWNING UTILITIES, EITHER OVERHEAD OR UNDERGROUND, WITHIN THE CONSTRUCTION AREA AND SHALL ARRANGE WITH THE UTILITY COMPANIES OF SAID UTILITIES. THE PROTECTION OR RELOCATION OF UTILITIES IS ULTIMATELY THE RESPONSIBILITY OF THE CONTRACTOR.
- 2. THE CONTRACTOR SHALL MAINTAIN EMERGENCY ACCESS TO ALL AREAS AFFECTED BY HIS WORK AT ALL TIMES.
- 3. ALL EXCAVATIONS SHALL BE THOROUGHLY SECURED ON A DAILY BASIS BY THE CONTRACTOR AT THE COMPLETION OF CONSTRUCTION OPERATIONS IN THE IMMEDIATE AREA.
- 4. EROSION CONTROL SYSTEMS SHALL BE INSTALLED AND MAINTAINED FOR THE DURATION OF THE PROJECT IN ACCORDANCE WITH APPLICABLE NHDES STANDARDS. THESE DETAILS SERVE AS A GUIDE ONLY.
- 5. REFER TO THE TOWN STANDARD DETAILS, LATEST REVISION, FOR ADDITIONAL INFORMATION AND CRITERIA.
- 6. THE CONTRACTOR SHALL STABILIZE ALL DITCHES, SWALES, AND BASINS PRIOR TO DIRECTING FLOW TO THEM.

EROSION CONTROL NOTES

- DURING CONSTRUCTION AND THEREAFTER, EROSION CONTROL MEASURES ARE TO BE IMPLEMENTED AS NOTED: 1. INSTALLATION OF SILTATION FENCES AND OTHER EROSION CONTROL MEASURES SHALL BE COMPLETED PRIOR TO THE START OF SITE WORK IN ANY GIVEN AREA. PREFABRICATED SILTATION FENCES SHALL BE INSTALLED ACCORDING
- . SILTATION FENCES AND OTHER EROSION CONTROL MEASURES SHALL BE KEPT CLEAN DURING CONSTRUCTION AND REMOVED WHEN ALL SLOPES HAVE A VEGETATIVE COVER OF GREATER THAN 85%. EROSION CONTROL MEASURES SHALL BE INSPECTED ON A WEEKLY BASIS AND AFTER EVERY RAINFALL.
- 3. EXISTING VEGETATION IS TO REMAIN UNDISTURBED WHEREVER POSSIBLE.
- 4. THE AREA OF LAND EXPOSED AND THE TIME OF EXPOSURE SHALL BE MINIMIZED, ALL DISTURBED AREAS SHALL BE STABILIZED WITHIN 72 HOURS AFTER FINAL GRADING.
- 5. ALL DISTURBED AREAS SHALL HAVE A MINIMUM OF 4" OF LOAM INSTALLED WITH NOT LESS THAN 1.1 POUNDS OF SEED MIX PER 1,000 SQ. FT. SEED MIXTURE SHALL BE:

1.1 LBS.

PERMANENT MIX: CREEPING RED FESCUE - 0.45 LBS. 0.20 LBS. BIRDSFOOT TREFOIL -

TO THE MANUFACTURER'S RECOMMENDATIONS.

- 6. LIME AND FERTILIZER SHALL BE INCORPORATED INTO THE SOIL PRIOR TO OR AT THE TIME OF AT THE TIME OF SEEDING, A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS. PER ACRE OF 10-20-20 SERVICES RECOMMENDATIONS
- '. HAY MULCH OR JUTE MATTING SHALL BE USED WHERE INDICATED ON THE PLANS. A MINIMUM OF 1.5 TONS OF MULCH PER ACRE SHALL BE APPLIED. MULCH SHALL BE ANCHORED IN PLACE WHERE NECESSARY. JUTE MATTING SHALL BE LAID IN THE DIRECTION OF RUNOFF FLOW AND APPLIED IN ACCORDANCE WITH MANUFACTURER'S
- 8. PERMANENT OR TEMPORARY COVER MUST BE IN PLACE BEFORE THE GROWING SEASON ENDS. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS AREA NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 15 TO SEPTEMBER 15. NO DISTURBED AREA SHALL BE LEFT EXPOSED DURING WINTER MONTHS.
- 9, CALCIUM CHLORIDE SHALL BE USED FOR DUST CONTROL IN APPROPRIATE AREAS.

CONSTRUCTION GENERAL PERMIT

- 1. THE OWNER, IN CONJUNCTION WITH THE CONTRACTOR (OPERATORS), NEEDS TO OBTAIN A CONSTRUCTION GENERAL PERMIT (CGP) FOR LARGE CONSTRUCTION ACTIVITIES (FIVE OR MORE ACRES) OR SMALL CONSTRUCTION ACTIVITIES (GREATER THAN ONE ACRE BUT LESS THAN FIVE ACRES) FROM THE ENVIRONMENTAL PROTECTION AGENCY (EPA). AS PART OF THE CGP, A STORM WATER NOTICE OF INTENT (NOI) WILL NEED TO BE SUBMITTED TO THE EPA AT LEAST 7 DAYS PRIOR TO COMMENCING CONSTRUCTION. THE NOI WILL NEED TO BE SUBMITTED TO STORM WATER NOTICE OF INTENT (4203M). USEPA, 1200 PENNSYLVANIA AVE. NW, WASHINGTON, DC 20460.
- 2. THE CGP OUTLINES A SET OF PROVISIONS MANDATING THE OWNER AND CONTRACTOR TO COMPLY WITH THE REQUIREMENTS OF THE NATIONAL POLLUTION DISCHARGE ELIMINATION SYSTEM (NPDES) STORM WATER REGULATIONS, INCLUDING, BUT NOT LIMITED TO, STORM WATER POLLUTION PREVENTION PLANS (SWPPP'S), IMPLEMENTATION OF EROSION AND SEDIMENTATION CONTROLS, EQUIPMENT MAINTENANCE GUÍDELINES, ETC. PLEASE CONTACT USEPA OFFICE OF WASTEWATER MANAGEMENT AT 202-564-9545 OR AT WWW.EPA.GOV/NPDES/STORMWATER FOR ADDITIONAL INFORMATION. IN ADDITION, ONE CAN CONTACT ABBY SWAINE OF NEW ENGLAND'S EPA REGION 1 AT 617-918-1841.

STORMWATER NOTES

- 1. PROPOSED IS EROSION CONTROL & STABILIZATION MEASURES FOR AN EXISTING GRAVEL PIT.
- 2. TOTAL AREA: 160± AC. TOTAL AREA OF DISTURBANCE: XX.X± AC.
- 3. STABILIZATION PRACTICES FOR EROSION AND SEDIMENTATION CONTROLS:

TEMPORARY STABILIZATION - TOPSOIL STOCKPILES AND DISTURBED AREAS OF THE CONSTRUCTION SITE THAT WILL NOT BE REDISTURBED FOR 21 DAYS OR MORE MUST BE STABILIZED BY THE 14TH DAY AFTER THE LAST DISTURBANCE. THE TEMPORARY SEED SHALL BE ANNUAL RYE APPLIED AT THE RATE OF 1.1 LBS PER 1,000 SQUARE FEET. PRIOR TO SEEDING, A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL LIMESTONE AND 500 LBS PER ACRE OF 10-20-20 FERTILIZER SHALL BE APPLIED. AFTER SEEDING, EACH AREA SHALL BE MULCHED WITH 1.5 TONS PER ACRE OF HAY MULCH. MULCH TO BE ANCHORED IN PLACE WHERE NECESSARY. AREAS OF THE SITE THAT WILL BE PAVED WILL TEMPORARILY BE STABILIZED BY APPLYING GEOTEXTILES AND A STONE SUB-BASE UNTIL BITUMINOUS PAVEMENT CAN BE APPLIED. CALCIUM CHLORIDE SHALL BE USED FOR DUST CONTROL IF NEEDED.

PERMANENT STABILIZATION — DISTURBED PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES PERMANENTLY CEASES SHALL BE STABILIZED WITH PERMANENT SEED NO LATER THAN 14 DAYS AFTER THE LAST CONSTRUCTION ACTIVITY. THE PERMANENT SEED MIX SHALL CONSIST OF 0.45 LBS/1,000 S.F. TALL FESCUE, 0.20 LBS/1,000 S.F. CREEPING RED FESCUE, AND 0.20 LBS/1,000 S.F. BIRDSFOOT TREFOIL. PRIOR TO SEEDING, A MINIMUM OF 2 TONS PER ACRE OF AGRICULTURAL IMESTONE AND 500 LBS PER ACRE IF 10—20—20 FERTILIZER SHALL BE APPLIED. AFTER SEEDING EACH AREA SHALL BE MULCHED WITH 1.5 TONS PER ACRE OF HAY MULCH. MULCH TO BE ANCHORED IN PLACE WHERE NECESSARY.

Copyright 2006 © Thomas F. Moran, Inc. 48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever

without the prior written permission of Thomas F. Moran, Inc. This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.

STORMWATER NOTES CONT.

4. STRUCTURAL PRACTICES FOR EROSION AND SEDIMENTATION CONTROL

SILT FENCE — WILL BE CONSTRUCTED AROUND THE PERIMETER OF THE DISTURBED AREAS AND WILL DELINEATE THE LIMITS OF WORK FOR THE PROPOSED CONSTRUCTION. THE SILT FENCE WILL BE INSTALLED BY STRETCHING REINFORCED FILTER FABRIC BETWEEN POSTS WITH AT LEAST 8 INCHES OF THE FABRIC BURIED BELOW THE GROUND SURFACE TO PREVENT GAPS FROM FORMING NEAR THE GROUND SURFACE. RUNOFF WILL FLOW THROUGH THE OPENINGS IN THE FILTER FABRIC WHILE RETAINING THE SEDIMENT WITHIN THE CONSTRUCTION AREA.

BLANKET SLOPE PROTECTION - SHALL BE INSTALLED ON ALL 2:1 SLOPES OR STEEPER ON SITE. ANCHOR THE TOP OF THE BLANKET BY ANCHORING THE BLANKET IN A 6" DEEP TRENCH. BACKFILL AND COMPACT TRENCH AFTER STAPLING. ROLL THE BLANKET IN THE DIRECTION OF STORM WATER FLOW. WHERE 2 OR MORE STRIPS OF BLANKET ARE REQUIRED, A MINIMUM OF 4" OF OVERLAP SHALL

STONE CHECK DAMS - WILL BE INSTALLED IN EXISTING AND PROPOSED GRASS SWALES TO REDUCE THE VELOCITY OF CONCENTRATED STORM WATER FLOWS AND PREVENT EROSION OF THE SWALE.

5. STORM WATER MANAGEMENT

- STORM WATER DRAINAGE FLOW PATTERNS WILL BE MAINTAINED ON-SITE.
- 6. ALL CONSTRUCTION DEBRIS AND WASTE MATERIALS SHALL BE COLLECTED AND STORED IN SECURE DUMPSTERS OR APPROVED ENCLOSURE AND REMOVED FROM THE SITE ON A WEEKLY BASIS. NO CONSTRUCTION WASTE SHALL BE BURIED ON SITE. PORTABLE TOILET SANITARY WASTE FACILITIES WILL BE PROVIDED DURING CONSTRUCTION AND MAINTAINED/DISPOSED OF ON A REGULAR BASIS IN ACCORDANCE WITH TOWN AND STATE REGULATIONS.

A LIST OF CONSTRUCTION ITEMS AND OTHER PRODUCTS USED ON THIS PROJECT SHALL BE KEPT ON RECORD WITH THIS PLAN ONSITE. ALL CHEMICALS, PETROLEUM PRODUCTS AND OTHER MATERIALS USED DURING CONSTRUCTION SHALL BE STORED IN A SECURE AREA, AND PRECAUTIONS USED T PREVENT POTENTIAL SOURCES OF CONTAMINATION OR POLLUTION. ANY SPILL OF THESE TYPES OF SUBSTANCES SHALL BE CLEANED UP AND DISPOSED OF IN A LEGAL MANNER AS SPECIFIED BY STATE REGULATIONS AND THE MANUFACTURER. ANY SPILL IN AMOUNTS EQUAL TO OR EXCEEDING

REPORTABLE QUANTITY AS DEFINED BY THE EPA SHALL TAKE THE FOLLOWING STEPS: - NOTIFY THE NATIONAL RESPONSE CENTER IMMEDIATELY AT (800) 424-8802; IN WASHINGTON, D.C., CALL (202) 426-2675.

- WITHIN 14 DAYS, SUBMIT A WRITTEN DESCRIPTION OF THE RELEASE TO THE EPA REGIONAL OFFICE PROVIDING THE DATE AND CIRCUMSTANCES OF THE

RELEASE AND THE STEPS TO BE TAKEN TO PREVENT ANOTHER RELEASE. - MODIFY THE POLLUTION PREVENTION PLAN TO INCLUDE THE INFORMATION LISTED ABOVE.

- 7. GOOD HOUSEKEEPING:
 THE FOLLOWING GOOD HOUSEKEEPING PRACTICES WILL BE FOLLOWED ONSITE DURING THE CONSTRUCTION PROJECT.
 - AN EFFORT WILL BE MADE TO STORE ONLY ENOUGH PRODUCT REQUIRED TO - ALL MATERIALS STORED ONSITE WILL BE STORED IN A NEAT, ORDERLY MANNER IN THEIR APPROPRIATE CONTAINERS AND, IF POSSIBLE, UNDER A ROOF OR - PRODUCTS WILL BE KEPT IN THEIR ORIGINAL CONTAINERS WITH THE ORIGINAL
 - MANUFACTURER'S LABEL;
 SUBSTANCES WILL NOT BE MIXED WITH ONE ANOTHER UNLESS RECOMMENDED
 - BY THE MANUFACTURER; - WHENEVER POSSIBLE, ALL OF A PRODUCT WILL BE USED UP BEFORE
 - DISPOSING OF THE CONTAINER: - MANUFACTURERS' RECOMMENDATIONS FOR PROPER USE AND DISPOSAL WILL BE - THE SITE SUPERINTENDENT WILL INSPECT DAILY TO ENSURE PROPER USE AND DISPOSAL OF MATERIALS ONSITE.
- HAZARDOUS PRODUCTS: THESE PRACTICES ARE USED TO REDUCE THE RISKS ASSOCIATED WITH HAZARDOUS MATERIALS.
- PRODUCTS WILL BE KEPT IN ORIGINAL CONTAINERS UNLESS THEY ARE NOT RESEALABLE: - ORIGINAL LABELS AND MATERIAL SAFETY DATA WILL BE RETAINED; THEY CONTAIN
- IMPORTANT PRODUCT INFORMATION; - IF SURPLUS PRODUCT MUST BE DISPOSED OF, MANUFACTURER'S OR LOCAL AND STATE RECOMMENDED METHODS FOR PROPER DISPOSAL WILL BE FOLLOWED.

PRODUCT SPECIFIC PRACTICES: THE FOLLOWING PRODUCT SPECIFIC PRACTICES WILL BE FOLLOWED ON SITE:

ALL ONSITE VEHICLES WILL BE MONITORED FOR LEAKS AND RECEIVE REGULAR PREVENTATIVE MAINTENANCE TO REDUCE THE CHANCE OF LEAKAGE. PETROLEUM PRODUCTS WILL BE STORED IN TIGHTLY SEALED CONTAINERS WHICH ARE CLEARLY LABELED. ANY ASPHALT SUBSTANCES USED ONSITE WILL BE APPLIED ACCORDING TO THE MANUFACTURER'S RECOMMENDATIONS.

FERTILIZERS USED WILL BE APPLIED ONLY IN THE MINIMUM AMOUNTS RECOMMENDED BY THE MANUFACTURER. ONCE APPLIED, FERTILIZER WILL BE WORKED INTO THE SOLID TO LIMIT EXPOSURE TO STORM WATER. STORAGE WILL BE IN A COVERED SHED. THE CONTENTS OF ANY PARTIALLY USED BAGS OF FERTILIZER WILL BE TRANSFERRED TO A SEALABLE PLASTIC BIN TO AVOID SPILLS

ALL CONTAINERS WILL BE TIGHTLY SEALED AND STORED WHEN NOT REQUIRED FOR USE. EXCESS PAINT WILL NOT BE DISCHARGED TO THE STORM SEWER BUT WILL BE PROPERLY DISPOSED OF ACCORDING TO MANUFACTURER'S INSTRUCTIONS OR STATE AND LOCAL REGULATIONS.

CONCRETE TRUCKS: EXCESS CONCRETE SHALL BE USED IN AREAS DESIGNATED BY THE SITE CONTRACTOR. WASH WATER SHALL BE DISPOSED OF USING BEST MANAGEMENT PRACTICES. BUILDING CONTRACTOR IS RESPONSIBLE FOR REMOVAL OF ALL DRUM WASH WATER ASSOCIATED WITH CONCRETE FOR THE BUILDING PAD. SITE CONTRACTOR TO COORDINATE AND PROVIDE BUILDING CONTRACTOR WITH AN AREA FOR DRUM WASH

SPILL CONTROL PRACTICES: IN ADDITION TO THE GOOD HOUSEKEEPING AND MATERIAL MANAGEMENT PRACTICES DISCUSSED IN THE PREVIOUS SECTIONS OF THIS PLAN, THE FOLLOWING PRACTICES WILL BE FOLLOWED FOR SPILL PREVENTION AND CLEANUP:

- MANUFACTURER'S RECOMMENDED METHODS FOR SPILL CLEANUP WILL BE CLEARLY POSTED AND SITE PERSONNEL WILL BE MADE AWARE OF THE PROCEDURES AND THE LOCATION OF THE INFORMATION AND CLEANUP SUPPLIES.


 - MATERIALS AND EQUIPMENT NECESSARY FOR SPILL CLEANUP WILL BE KEPT IN THE MATERIAL STORAGE AREA ONSITE, EQUIPMENT AND MATERIALS WILL INCLUDE BUT NOT BE LIMITED TO BROOMS, DUST PANS, MOPS, RAGS, GLOVES, GOGGLES, KITTY LITTER, SAND, SAWDUST, AND PLASTIC AND METAL TRASH CONTAINERS
- SPECIFICALLY FOR THIS PURPOSE.

 ALL SPILLS WILL BE CLEANED UP IMMEDIATELY AFTER DISCOVERY. - THE SPILL AREA WILL BE KEPT WELL VENTILATED AND PERSONNEL WILL WEAR APPROPRIATE PROTECTIVE CLOTHING TO PREVENT INJURY FROM CONTACT WITH A
- SPILLS OF TOXIC OR HAZARDOUS MATERIAL WILL BE REPORTED TO THE APPROPRIATE STATE OR LOCAL GOVERNMENT AGENCY, REGARDLESS OF SIZE. THE SPILL PREVENTION PLAN WILL BE ADJUSTED TO INCLUDE MEASURES TO PREVENT THIS TYPE OF SPILL FROM REOCCURRING AND HOW TO CLEAN UP THE SPILL IF THERE IS ANOTHER ONE. A DESCRIPTION OF THE SPILL, WHAT CAUSED IT, AND THE CLEANUP MEASURES WILL ALSO BE INCLUDED.

 THE SITE SUPERINTENDENT RESPONSIBLE FOR THE DAY—TO—DAY SITE OPERATIONS, WILL BE THE SPILL PREVENTION AND CLEANUP COORDINATOR. THEY WILL DESIGNATE AT LEASE THREE OTHER SITE PERSONNEL WHO WILL EACH RECEIVE SPILL PREVENTION AND CLEANUP TRAINING. THESE INDIVIDUALS WILL


EACH BECOME RESPONSIBLE FOR A PARTICULAR PHASE OF PREVENTION AND CLEANUP. THE NAMES OF RESPONSIBLE SPILL PERSONNEL WILL BE POSTED IN THE MATERIAL STORAGE AREA AND IN THE OFFICE TRAILER ONSITE.


- 8. THE CONTRACTOR IS RESPONSIBLE TO MAINTAIN RECORDS OF CONSTRUCTION ACTIVITIES, INCLUDING DATES OF MAJOR GRADING ACTIVITIES, DATES WHEN CONSTRUCTION ACTIVITIES HAVE TEMPORARILY CEASED ON A PORTION OF THE SITE, DATES WHEN WORK IS COMPLETED ON A PORTION OF THE SITE, and dates when stabilization measures are initiated onsite.
- 9. THE CONTRACTOR SHALL PERFORM INSPECTIONS OR HAVE A CONSULTING ENGINEER PERFORM INSPECTIONS EVERY SEVEN (7) DAYS OR WITHIN 24 HOURS AFTER A STORM OF 0.5 INCH OR greater, inspections reports are to be kept on file at the site with this plan. MAINTENANCE OR MODIFICATION SHALL BE IMPLEMENTED AND ADDED TO THE PLAN AS RECOMMENDED By the qualified inspector.



SILT FENCE


NOT TO SCALE





STONE CHECK DAM

NOT TO SCALE




REDI-ROCK RETAINING WALL

REINFORCED WITH GEOGRID

SCALE: 1/2"=1'-0"

REV. DATE

DESCRIPTION



2. ROLL THE BLANKET DOWN THE SWALE IN THE DIRECTION OF THE WATER FLOW.

3. THE EDGES OF BLANKETS MUST BE STAPLED WITH APPROX. 4 INCH OVERLAP WHERE 2 OR MORE STRIP WIDTHS ARE REQUIRED.

4. WHEN BLANKETS MUST BE SPLICED DOWN THE SWALE, PLACE BLANKET END OVER END WITH 6 INCH (MIN.) OVERLAP AND ANCHOR DOWN SLOPE BLANKET IN A 6 INCH DEEP TRENCH.

5. BLANKET SHALL BE NORTH AMERICAN GREEN SC-150 OR APPROVED EQUAL.

BLANKET SLOPE PROTECTION

FOR EROSION CONTROL


NOT TO SCALE

CONSTRUCTION SPECIFICATIONS

- 1. THE SUBGRADE FOR THE FILTER MATERIAL, GEOTEXTILE FABRIC OR RIP—RAP SHALL BE CLEARED AND GRUBBED TO REMOVE ALL ROOTS, VEGETATION, AND DEBRIS AND PREPARED TO THE LINES AND GRADES SHOWN ON THE
- 2. THE ROCK AND/OR GRAVEL USED FOR FILTER AND RIP—RAP SHALL CONFORM TO THE SPECIFIED GRADUATION.
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM ROCK RIP-RAP BY PLACING A CUSHION OF SAND AND PUNCTURE OR TEARING DURING PLACEMENT OF THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF GRAVEL OVER THE FABRIC. DAMAGED AREAS IN THE FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP—RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT DISPLACEMENT OF THE UNDERLYING MATERIALS. HAND PLACEMENT MAY BE REQUIRED TO PREVENT DAMAGE TO ANY PERMANENT STRUCTURES.
- 5. STONES FOR RIP-RAP SHALL BE ANGULAR OR SUBANGULAR. THE STONES SHOULD BE SHAPED SO THAT THE LEAST DIMENSION OF THE STONE FRAGMENT SHALL BE NOT LESS THAN ONE—THIRD OF THE GREATEST DIMENSION OF THE FRAGMENT. FLAT ROCKS SHALL NOT BE USED AS RIP—RAP.
- 6. VOIDS IN THE ROCK RIP-RAP SHOULD BE FILLED WITH SPALLS AND SMALLER ROCKS.

MAINTENANCE

- 1. ROCK RIP-RAP SHOULD BE CHECKED AT LEAST ANNUALLY AND AFTER EVERY MAJOR STORM. IF THE RIP-RAP HAS BEEN DISPLACED, UNDERMINED OR DAMAGED, IT SHOULD BE REPAIRED IMMEDIATELY BEFORE FURTHER DAMAGE CAN TAKE PLACE. WOODY VEGETATION SHOULD BE REMOVED FROM THE ROCK RIP-RAP ANNUALLY.
- 2. IF THE RIP-RAP IS ON A CHANNEL BANK THE STREAM SHOULD BE KEPT CLEAR OF OBSTRUCTIONS.
- 3. REPAIRS MUST BE CARRIED OUT IMMEDIATELY TO AVOID ADDITIONAL DAMAGE TO THE RIP-RAP.



RIP RAP SWALE

NOT TO SCALE

MAY 25, 2006

PROGRESS PRINT

DECEMBER 11, 2006


TAX MAP 2 LOTS 5-59, 5-68, 5-71, 5-73, 5-74 DETAIL SHEET

> **RAYMOND PARK** 419 MAMMOTH ROAD PELHAM, NH

OWNED BY AND PREPARED FOR

TOWN OF PELHAM 6 VILLAGE GREEN, PELHAM, NH 03076

SCALE: AS NOTED





Civil Engineers Structural Engineers

48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747

www.tfmoran.com Bedford, NH • Manchester, NH • Keene, NH • Salem, NH • Portsmouth, NH

CK JK CADFILE 17265-00 Details






Copyright 2006 ©Thomas F. Moran, Inc.

48 Constitution Drive, Bedford, N.H. 03110

All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc.

This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.



PROGRESS PRINT

DECEMBER 11, 2006

TAX MAP 2 LOTS 5-59, 5-68, 5-71, 5-73, 5-74 DETAIL SHEET

RAYMOND PARK 419 MAMMOTH ROAD PELHAM, NH

OWNED BY AND PREPARED FOR

TOWN OF PELHAM 6 VILLAGE GREEN, PELHAM, NH 03076

MAY 25, PAUS SCALE: AS NOTED


REV. DATE DESCRIPTION


F	DD AL
Bedford,	NH • Manche
,	


Civil Engineers Structural Engineers Traffic Engineers


48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747


ester, NH • Keene, NH • Salem, NH • Portsmouth, NH











- 1. THE SUBGRADE FOR THE GEOTEXTILE FABRIC AND RIP-RAP SHALL BE PREPARED TO THE LINES AND GRADES
- 2. THE ROCK USED FOR RIP-RAP SHALL CONFORM TO THE SPECIFIED GRADATION.
- 3. GEOTEXTILE FABRICS SHALL BE PROTECTED FROM PUNCTURE OR TEARING DURING THE PLACEMENT OF THE ROCK RIP—RAP. DAMAGED AREAS IN THE FABRIC SHALL BE REPAIRED BY PLACING A PIECE OF FABRIC OVER THE DAMAGED AREA OR BY COMPLETE REPLACEMENT OF THE FABRIC. ALL OVERLAPS REQUIRED FOR REPAIRS OR JOINING TWO PIECES OF FABRIC SHALL BE A MINIMUM OF 12 INCHES.
- 4. STONE FOR THE RIP—RAP MAY BE PLACED BY EQUIPMENT AND SHALL BE CONSTRUCTED TO THE FULL LAYER THICKNESS IN ONE OPERATION AND IN SUCH A MANNER AS TO PREVENT SEGREGATION OF THE STONE SIZES.

OUTLET APRON

NOT TO SCALE

CONSTRUCTION SPECIFICATIONS:

PREPARE BEDDING:

BACKFILL MATERIAL AROUND THE END SECTION MAY BE THE SAME AS THE MATERIAL AROUND THE PIPE, PLACE A FEW INCHES OF BACKFILL MATERIAL IN THE TRENCH OR DITCH WHERE THE END SECTION WILL BE PLACED. COMPACT AND CONTOUR THIS BEDDING MATERIAL TO GENERALLY MATCH THE END SECTION, EXCAVATE AN AREA IN THE BEDDING WHERE TOE TROUGH WILL SEAT SO THAT THE END SECTION WILL BE LEVEL WITH THE BOTTOM OF THE TRENCH OR DITCH IN THE FINISHED INSTALLATION.


OPEN THE END SECTION COLLAR AND SEAT IT OVER THE TWO PIPE CONNECTIONS. ONCE THE END SECTION IS POSITIONED, CHECK TO MAKE SURE THAT THE INVERT OF THE END SECTION MATCHES THE INVERT OF THE PIPE AND THAT THE END SECTION IS LEVEL WITH THE TRENCH OR DITCH BOTTOM.

SLIP THE STAINLESS STEEL ROD THROUGH THE PRE-DRILLED HOLES AT THE TOP OF THE COLLAR. THE ROD SHOULD BE BETWEEN THE CROWNS OF THE TWO PIPE CONNECTIONS. PLACE A WASHER ON EITHER END OF THE ROD. PLACE A NUT ON EITHER END OF THE ROD AND TIGHTEN WITH A

SECURE THE TOE TROUGH:

TO PREVENT WASHOUTS FROM HIGH VELOCITY FLOW, IT IS RECOMMENDED THAT THE TROUGH BE SECURED WITH CONCRETE. POUR CONCRETE IN THE TROUGH UP TO THE LEVEL OF THE TRENCH OR DITCH BOTTOM AND ALONG THE ENTIRE LENGTH OF THE TROUGH. FINISH BACKFILL:

SHOVEL BACKFILL AROUND THE END SECTION IN 6 TO 9 INCH LAYERS EQUALLY ON BOTH SIDES, KNIFING IT TO ELIMINATE VOIDS. TAMP WITH A SMALL-FACED COMPACTOR OR OTHER EQUIPMENT SUITABLE FOR SMALL AREAS. CONTINUE PLACING, KNIFING, AND COMPACTING BACKFILL LAYERS TO THE TOP OF THE END SECTION TO SEAT IT WELL INTO THE BACKFILL.





	DIMENSIONS, INCHES (mm)					
PIPE DIAMETER	PART NO.	A, ±1 (25)	B MAX	H, ±1 (25)	L, ±1/2 (13)	W, ±2 (50)
12", 15" (300,375)	1210 NP	6.5 (165)	10 (254)	6.5 (165)	25 (635)	29 (736)
18" (450)	1810 NP	7.5 (190)	15 (380)	6.5 (168)	32 (812)	35 (890)
24" (600)	2410 NP	7.5 (190)	18 (450)	6.5 (165)	36 (900)	45 (1140)
30" (750)	3010 NP	10.5 (266)	NA.	7.0 (178)	53 (1346)	68 (1725)
36" (900)	3610 NP	10.5 (266)	NA	7.0 (178)	53 (1346)	68 (1725)

FLARED END SECTION

HIGH DENSITY POLYETHYLENE (HDPE)

NOT TO SCALE





CONCRETE WHEELSTOP

NOT TO SCALE

TAX MAP 2 LOTS 5-59, 5-68, 5-71, 5-73, 5-74 **DETAIL SHEET**

RAYMOND PARK 419 MAMMOTH ROAD

PELHAM, NH OWNED BY AND PREPARED FOR

TOWN OF PELHAM

6 VILLAGE GREEN, PELHAM, NH 03076

SCALE: AS NOTED MAY 25, 2006



Civil Engineers

48 Constitution Drive Bedford, NH 03110 Phone (603) 472-4488 Fax (603) 472-9747

Bedford, NH . Manchester, NH . Keene, NH . Salem, NH . Portsmouth, NH SHEET 13 OF 13

PROGRESS PRINT

DECEMBER 11, 2006

REV.	DATE	DESCRIPTION	DR	CK
	-			

Copyright 2006 ©Thomas F. Moran, Inc. 48 Constitution Drive, Bedford, N.H. 03110 All rights reserved. These plans and materials may not be copied, duplicated, replicated or otherwise reproduced in any form whatsoever without the prior written permission of Thomas F. Moran, Inc. This plan is not effective unless signed by a duly authorized officer of Thomas F. Moran, Inc.